


4584

4584



LEGEND

● = MONUMENT FOUND AS NOTED

NARRATIVE:

THIS SURVEY WAS ACCOMPLISHED AT THE REQUEST OF HANCOCK
TIMBER RESOURCE GROUP TO MARK AND MONUMENT THE BOUNDARY
LINES SHOWN.

--THE BEARINGS ARE BASED ON A COMPASS BEARING TAKEN AT THE
SOUTHEAST CORNER OF SECTION 17.

--THE SOUTH 1/4 CORNERS OF SECTIONS 17 AND 18 WERE SEARCHED FOR
AND DETERMINED TO BE LOST.

--ALL REFERENCES WERE MEASURED WITH A HAND COMPASS SET AT
DECLINATION 21° EAST AND A STEEL TAPE. ALL NEW BEARING TREES
WERE MEASURED TO THE HEAD OF A 3" TRACK SPIKE SET IN THE BASE
BLAZE OF 4 BLAZES UP THE FACE. BEARING TREE TAGS WERE PLACED AT
SHOULDER HEIGHT ABOVE THE BLAZES.

--THE LINES WERE MARKED WITH RED AND WHITE RIBBON, METAL
BOUNDARY REFERENCE TAGS PLACED IN A SLICE AT LOWEST PART OF
ROOT CROWN AT APPROXIMATELY 50' INTERVALS. TREES WITHIN 8' OF
LINE WERE BLAZED AT CHEST HEIGHT. TREES LOCATED ON THE
BOUNDARY LINE WERE MARKED WITH TWO BLAZES ON THE BOUNDARY
LINE ON BOTH SIDES OF THE TREE.

<p>REGISTERED PROFESSIONAL LAND SURVEYOR</p> <p><i>Leslie G. Keenon</i></p> <p>OREGON JULY 30, 1976 LESLIE G. KEENON 1080 RENEWAL DATE 6/30/99</p>	<p>KEENON LAND SERVICES</p> <p>1224 ALDER ST. VERNONIA, OR 97064 (503) 429-6115</p>	<p>SURVEY FOR HANCOCK TIMBER RESOURCES GROUP IN SECTIONS 17, 18, 19, AND 20 T5N, R4W, W.M. COLUMBIA COUNTY, OREGON SCALE 1" = 600' DEC. 11, 1998</p>	<p>COLUMBIA COUNTY SURVEYORS OFFICE</p> <p>RECEIVED <u>3-4-99</u> ACCEPTED <u>3-30-99</u> CHECK # <u>339</u></p>
DRAWN BY: VSS	FIELD: MM/TH	EQUIPMENT: GTS300/TDS48 JOB No. 98-142 PROJECT No. 98-142	REVISED:

4584